



Loading Data for ASTM F891 Foam Core DWV Pipe

| NOMINAL PIPE SIZE | OUTSIDE DIAMETER | JOINTS PER BUNDLE | FEET PER BUNDLE | FEET PER TRUCKLOAD |
|------------------------------------|------------------|-------------------|-----------------|--------------------|
| Schedule 40 – 10' | | | | |
| 1½" | 1.900 | 315 | 3,150 | 100,800 |
| 2" | 2.375 | 210 | 2,100 | 67,200 |
| 3" | 3.500 | 92 | 920 | 29,440 |
| 4" | 4.500 | 57 | 570 | 18,240 |
| 6" | 6.625 | 24 | 240 | 7,680 |
| Schedule 40 – 20' | | | | |
| 1½" | 1.900 | 315 | 6,320 | 100,800 |
| 2" | 2.375 | 210 | 4,200 | 67,200 |
| 3" | 3.500 | 92 | 1,840 | 29,440 |
| 4" | 4.500 | 57 | 1,140 | 18,240 |
| 6" | 6.625 | 24 | 480 | 7,680 |
| Schedule 40 – 20' Half Rack | | | | |
| 1½" | 1.900 | 158 | 3,160 | 88,480 |

Note: These dimensions are for estimating purposes only

Rev: 05/2010